



ACO Infrastructure

KerbDrain QK200B

PORTFOLIO

Carrington Road

For the Auckland Transport roading upgrade ACO's KerbDrain QK200B was installed in the first week of July 2019. The main reason KerbDrain was used in this project was due to the major services, mainly gas, running through the area, excavating to get to the stormwater outlets was too prohibitive. The KerbDrain allowed continuous capture of water along the run and the capability to slow the flow and release the water to flow along existing Kerb to the existing stormwater collection pit.



Benefits

- The access unit with aluminium lid allows easy access for maintenance.
- One-piece unit design for lifetime integrity and security.
- Profiled side walls and strengthening ribs provide channel strength and anchorage to surrounding concrete.
- Certified to AS 3996 Class D loading.



www.aconz.co.nz

